
## WIFI Installation Guide



Remove the metal plate as shown in below Figure.




Open APP and choose "Bluetooth", click BLExxxx to login. Then click the function list and choose Setting.



2

Take out WIFI module from fitting bag, and connect the exposed WIFI interface to DB9 terminal, and check that the connection is well with an appropriate force.



4

Click switch user, enter password "admin" to login with administrator account.

Click WIFI Setting to enter WIFI router name & password.





WIFI module need 10 to 15 seconds to connect with WIFI router. After WIFI Setting finish, APP will show the result: "WIFI Connected" means connection successful. "WIFI Setting Failed" means connection failed.

If WIFI connection failed, repeat step 4 & 5.









Connecting WIFI...

WIFI Connected WIFI Setting Failed



Bind the cloud account using APP referring to the appendix.



Register a cloud account refer to appendix (Referring to appendix).



Remove the locking screws on the bottom of the PV inverter, and take down the metal plate.

