

Fox 5 BOM (Sample)

| Description | Qty | |
|-----------------------|------------|--|
| 4mm Solar cable Black | 100 | Depending on panel location |
| 4mm solar cable Red | 100 | Depending on panel location |
| 4mm Earth cable | 80 | Depending on inverter & panel location |
| 4mm Twin and Earth | 30 | Depending on inverter location- Separate earth needs to be run |
| 32A 2p Din rail | 4 | Depending on DB (Could be Samite DB) |
| Male Mc4 | 20 | Rough quantity |
| Female Mc4 | 20 | Rough quantity |
| 10 Way DB | 1 | If no space in DB |
| 60A/63A change over | 1 | To bypass EPS loads |
| 63A Earth leakage | 1 | If an additional earth leakage is needed |
| Fuse holder | 8 | Depending on the number of strings |
| DC Fuse | 8 | Depending on the number of strings |
| Boot lace Ferrules | 16 | Depending on the number of Fuses |
| Surge Protectors AC | 2 | Depending on the electrician's discretion |
| Surge Protectors DC | 2 | Depending on the electrician's discretion |

*Please note, If you use 40A rather than 32A MCB's please use 6mm wire